



16755 Finley Butte Rd • P.O. Box 127 • LaPine, OR 97739
541-536-2126 • 800-722-7219 • Fax 541-536-1423
www.midstateelectric.coop

Heat Pump & Duct Sealing Rebate Program

The following information is included in this information packet:

- Heat Pump & Duct Sealing Rebate Program Procedures and Requirements
- Heat Pump & Duct Sealing Contractors List
- Heat Pump & Duct Sealing Inspection Request


Procedures

1. It is your responsibility to contact the installer(s) to visit your home and provide you with a bid for the work to be completed. We recommend at least two bids, preferably three, but this is not a requirement.
2. Midstate will retain one copy of the signed bid sheet, you will receive a copy and the installer will retain a copy for their records. An accurate heat loss/gain analysis will accompany the bid, as well as a copy of the manufacturer's specifications on the equipment. It is then your responsibility to notify the contractor that you have accepted their bid.
3. Once the installation is complete, the installer will submit the required documentation to Midstate and a Midstate representative will then contact you to schedule an inspection.
4. Midstate will perform an inspection to verify the work was completed properly. After passing the inspection, Midstate Electric will issue a check for the rebate amount.

Requirements

1. The installation shall meet all State and Local code requirements.
2. The heat pump will be sized by using a balance point of no more than 30 degrees Fahrenheit, preferably less, using a heat loss/gain analysis provided by the installer and approved by Midstate. Commissioning of the heat pump shall be performed and the approved form submitted to Midstate by a PTCS certified heat pump technician. Refer to the PTCS Heat Pump Commissioning Startup Form for the specific equipment and testing that is required.
3. The heat pump equipment must have an HSPF rating of not less than 9.0, and a SEER rating of not less than 14.0. **Exceptions:** Geothermal systems must have a C.O.P. rating of not less than 3.0.
4. New and existing duct systems shall meet PTCS specifications if determined "leaky enough". For existing duct systems: it is determined "leaky enough" if the tested leakage to the outside value is greater than the lessor of 250 CFM or 15% of floor area.
5. Documentation to be submitted to Midstate include: Heat loss calculation of home, Heat Pump & Duct Sealing Inspection Request Form, manufacturer's specifications on equipment, balance point graph, PTCS Heat Pump Commissioning Startup Form, PTCS Duct Testing Form (ODOE forms), and a copy of the invoice.



A Touchstone Energy® Cooperative 

16755 Finley Butte Rd • P.O. Box 127 • LaPine, OR 97739
541-536-2126 • 800-722-7219 • Fax 541-536-1423
www.midstateelectric.coop

HEATPUMP & DUCT SEALING CONTRACTOR LIST

[ACCUAIR INC](#)

541-504-8400
American Standard
PTCS Heat Pump & Duct Test Certified

[AFFORDABLE COMFORT SOLUTIONS](#)

541-480-3488
Daikin • Mitsubishi • Fujitsu
PTCS Heat Pump & Duct Test Certified

[AIRTECH](#)

541-536-2463
American Standard • Coleman Water Furnace
PTCS Heat Pump & Duct Test Certified

[BEND HEATING & SHEETMETAL INC](#)

541-382-1231
Carrier
PTCS Heat Pump & Duct Test Certified

[BEND PLUMBING & HEATING INC](#)

541-382-8577
PTCS Heat Pump & Duct Test Certified

[CASCADE HEATING & SPECIALTIES, INC.](#)

541-382-8483
Trane & Mitsubishi
PTCS Heat Pump & Duct Test Certified

[CENTRAL OREGON HEATING & COOLING](#)

541-923-1855 or 800-410-1855
Carrier • Daikin
PTCS Heat Pump & Duct Test Certified

[COMFORT FLOW HEATING](#)

541-726-0100
Trane • Mitsubishi • Water Furnace
PTCS Heat Pump & Duct Test Certified

[JUST KOMFORT HEATING & COOLING](#)

458-233-3406
Lennox • Goodman
PTCS Heat Pump & Duct Test Certified

[DESCHUTES HEATING & COOLING](#)

541-382-0424
PTCS Heat Pump & Duct Test Certified

[DIVERSIFIED HEATING & COOLING INC](#)

541-388-0368
Rheem
PTCS Heat Pump & Duct Test Certified

[HOME HEATING & COOLING](#)

541-389-4663
Amana • Coleman • Mitsubishi
PTCS Heat Pump & Duct Test Certified

[MOUNTAIN VIEW HEATING](#)

541-389-6714
Goodman • Lennox • Hallowell
PTCS Heat Pump & Duct Test Certified

[PROFESSIONAL HEATING & COOLING INC.](#)

541-923-3366
American Standard
PTCS Heat Pump & Duct Test Certified

[QUALITY HEATING](#)

541-923-4752 or 800-300-4752
Trane • Coleman
PTCS Heat Pump & Duct Test Certified

[SKY HEATING & AIR CONDITIONING](#)

541-316-7077
Trane
PTCS Heat Pump & Duct Test Certified

[STEPHENS HEATING & COOLING](#)

541-447-2150
Daikin • Mitsubishi • Goodman • Climate Master
PTCS Heat Pump Certified

[TRI COUNTY CLIMATE CONTROL](#)

541-923-2565
Carrier
PTCS Heat Pump & Duct Test Certified



16755 Finley Butte Rd • P.O. Box 127 • LaPine, OR 97739
541-536-2126 • 800-722-7219 • Fax 541-536-1423
www.midstateelectric.coop

Heat Pump & Duct Sealing Inspection Request

Member's name: _____

Address of installation: _____

Mailing address, if different: _____

City: _____ State: _____ Zip Code: _____ Phone #: _____

Installer: _____

Installer's business address: _____

City: _____ State: _____ Zip Code: _____ Phone #: _____

Equipment installed as listed below:

Outdoor Unit

Indoor Unit/Coil

Make _____

Model Number _____

Serial Number _____

Size (Ton/BTUH) _____ HSPF _____ SEER _____

Type of Duct System: Existing Duct System New Duct System New Construction

PLEASE INCLUDE THE APPROPRIATE OREGON DEPARTMENT OF ENERGY FORMS

This is to notify Midstate Electric Cooperative, Inc., that the installation of the item above is complete and ready for inspection.

____ Rebate customer (installer invoiced customer for full amount)

____ Rebate installer as per attached invoice (installer already rebated customer)

I am satisfied with the installation and authorize Midstate Electric to make payment.

Member's Signature _____ Date _____

Inspected By _____ Date _____